The 25 GeV Proton Synchrotron of the European Organization for Nuclear Research has now been put into operation. Towards the end of November 1959 protons were accelerated up to 24 GeV kinetic energy and a few weeks later, after adjustments had been made to the shape of the magnetic field at field values above 12 000 gauss by means of pole face windings, the maximum energy was increased to 28 GeV. The intensity of the accelerated beam of protons was measured as 10^{10} protons per pulse and there was no noticeable loss of particles during the whole acceleration period up to the maximum energy. The CERN Proton Synchrotron has thus fulfilled the expectations of its designers and the hopes of the twelve European countries that have supported the work for the past six years. It seems appropriate on this occasion to give a short account of this project together with a brief description of some of the design problems and preliminary measurements of the operating characteristics of this accelerator.

In June of 1952, at a conference in Copenhagen, the Interim Council of CERN decided to start an engineering design study of a 10 GeV proton synchrotron that was to be the principal high energy accelerator for nuclear physics research in Europe. The cost of this machine was considered to be so large in relation to other expenditures in physics research that no one European country felt justified in financing it alone. Hence several countries had combined their resources in order that physicists should have available in Europe the highest energy accelerator that was thought feasible at that time. By July 1952 a design group of three people was set up with Dr. O. Dahl in charge, and in August this group, during a visit to Brookhaven on Long Island to see the Cosmotron at first hand, learnt of a new idea for making cheaper and higher energy machines. This idea was considered so attractive that in October 1952 the CERN Council was persuaded to drop the engineering study of a 10 GeV proton synchrotron and instead to set up a theoretical study of the new principle. It seemed that a 30 GeV machine might be built for the same cost as a 10 GeV Cosmotron type of machine. It is interesting to note that at this time, and quite unknown to the western world, Russian scientists were planning a scaled-up version of the Berkeley Bevatron for 10 GeV.

In December 1952 the Proton Synchrotron Group was formed to aug-

The CERN Pro

ment the original staff of three and the members of this group, most of them honorary part-time members, remained in their own laboratories and institutes. Members of the theoretical section worked at A.E.R.E., Harwell and at the Universitetets Institut for Teoretisk Fysik, Copenhagen. The magnet studies were concentrated in the Laboratoire de Radioélectricité de l'Université, Paris. The radio frequency problems were studied at the Institut für Physik, Max-Planck-Institut, Heidelberg. The radiation shielding problems at such high energies were worked out using cosmic ray data at the Physikalisches Institut der Universität, Freiburg-i.B., Germany and the general engineering problems remained at the Chr. Michelsens Institutt, Bergen, Norway, where for six months two of the senior staff of the Cosmotron, J.P. Blewett and M.H. Blewett, gave invaluable assistance with the general design problems of the new machine.

By October 1953 enough was known about the implications of the new idea to present a tentative design of an accelerator to the Council of CERN. In America, meantime, the Brookhaven group and another at

M.I.T., Boston had been working on similar problems. At the end of October a conference was held at the Institute of Physics of the University of Geneva, to which were invited representatives of the American groups, the scientific members of the Council of CERN and other European scientists. The CERN Proton Synchrotron Group gave a series of lectures on its work of the previous ten months and presented a design for a 30 GeV proton synchrotron using the new alternating gradient principle. It was found that the Brookhaven group had arrived independently at a very similar design.

Immediately after this conference the CERN Council fixed the energy of the machine at 25 GeV and agreed that the members of the PS Group should come together in Geneva, near which city the new European laboratory was to be sited. The State of Geneva and the University generously offered temporary laboratory accommodation and by December 1953 most of the group had moved to Geneva with their families, and the task of designing the final machine started. Soon after this move Dr. O. Dahl resigned as Director of the group, and the group suffered a fur-

O. Dahl and F. Goward, respectively second and fourth from left to right on this photograph, were the first to be in charge of designing the CERN proton synchrotron. This picture shows them in 1952 with G. Collins and R. Wideroe, in the Cosmotron control room at Brookhaven.

ton Synchrotron

ther loss by the sudden death of Dr. F. Goward who had been acting as Deputy Director. Despite these initial set-backs the group successfully established itself in Geneva, which for nearly all the members and their families was a foreign city. From the beginning of 1954 onwards staff was steadily recruited from all over Europe and the group was built up as shown in the following table :

End of Year	Main Activities	Total staff *
1953	Preliminary studies. . .	20
1954	Design of final machine .	75
1955	Development of component parts	120
1956	Major contracts placed for components	150
1957	Manufacturing of components in firms	163
1958	Assembly of components at CERN	176
1959	Testing of components and commissioning of CPS	180

* This includes all staff directly connected with the design and construction of the machine.

The Alternating Gradient Principle has been described many times. The original idea was published by E.D. Courant, M.S. Livingston and H.S. Snyder ⁽¹⁾ and, quite unbeknown to these authors, was previously invented by N. Christofilos. In the conventional synchrotron the focusing of the circulating particles is achieved by arranging that the magnetic field, which guides the particles around a fixed radius, decreases slightly with radius. The amount of focusing achieved in this way is not very great, and consequently the amplitudes of the free oscillation of the particles are large and the dimensions of the magnet gap correspondingly large. Most of the cost in the original synchrotrons is in the magnet ; for example, the Russian 10 GeV Synchro-phasotron magnet, whose radius is 30.5 m, contains 35 000 tons of steel and the magnet gap is 150

cm wide and 40 cm high. Although greater focusing can be obtained in the axial direction by increasing the gradient of the magnetic field, the criterion for radial stability is then violated. It is the great advantage of the alternating gradient principle that the focusing of the circulating particles can, in theory, be made as strong as one wishes and the amplitudes of oscillation of the particles as small as desired. This is achieved by alternating the sign of the gradient of the magnetic field many times around the circumference of the machine. The net result of this stronger focusing is to reduce greatly the weight of the magnet ; for example, the CERN 25 GeV Proton synchrotron magnet has a useful aperture of 14 cm x 7 cm and contains only 3 400 tons of steel. It is 100 m in radius, that is 3 times the radius of the Russian machine and one tenth the steel weight.

These attractive advantages are realized at the price of greatly increased accuracy in manufacturing and aligning the magnet of the synchrotron. Also, once the magnet is set up with the required precision, it must remain in place and, for a machine 200 m in diameter, this presents some interesting foundation problems. The CERN Proton Synchrotron (CPS) magnet is made up of 100 supposedly identical magnet units, each about 4.3 m long. The magnetic field error between these units for the same energizing current should not exceed about one part per thousand, and the units should be set up with a precision of a few parts per million (0.3 mm in 100 m

radius). The units are mounted on a free floating monolith ring of concrete 200m in diameter and 2m x 2m in cross-section, and the machine is built in a subterranean annular tunnel in which the temperature is controlled to $\pm 1^\circ\text{C}$. As a further precaution, the concrete ring has steel pipes cast in it and water is passed round the ring to prevent any part assuming a temperature different from the rest. The technology developed for the magnet construction and the foundations has been described in various CERN reports. ⁽²⁾ ⁽³⁾

Another advantage of the alternating gradient principle is that the amplitude of momentum oscillations is very much smaller than in the conventional synchrotron. Since these momentum oscillations result in radial movements of the particles in the synchrotron which have to be contained within the width of the magnet aperture, the alternating gradient synchrotron is again more economical in magnet aperture than the conventional synchrotron, in this case by a factor of about 60. Unfortunately, this improvement is also realized at the cost of imposing problems which, at the time of designing the CPS, seemed formidable.

One restriction concerns the curious behaviour of the machine at an energy called the "transition energy". During the momentum oscillations in a synchrotron, particles with greater momentum than the mean value swing out to a radius greater than the mean radius. The revolution time of these particles depends on two factors which work in opposition. Because these particles

have a greater momentum than the mean value, their velocity is greater than the mean velocity and they take a shorter time to complete a revolution than the mean revolution time. On the other hand, since the radius at which these particles circulate is greater than the mean radius, they have a longer path to go round and this lengthens their revolution time. In an ordinary synchrotron, the "radius term" is greater than the "velocity term" and those particles with greater momentum than the mean value always take longer to go round than the mean particles. Due to the momentum compaction in an alternating gradient synchrotron, the radial displacement for a given momentum change is about a factor of 60 less than in a conventional synchrotron with the result that at low energies, at the beginning of the acceleration cycle, the velocity term is larger than the radius term. However, as the energy increases and the

but this can only be done by increasing the circumference of the machine by as much as 50%, with a consequent increase in cost. In fact, two new Russian alternating gradient machines have been designed in this way. However, in the case of the CPS it was calculated that the transition energy could be passed without loss of particles, and the operational results shown by the traces on fig. 1 justify these calculations. It is possible that the Russian machines will now be modified and consequently will be capable of going to even higher energies.

The particles in a synchrotron circulate at a fixed mean radius, and in order to keep them in the centre of the vacuum chamber during the whole acceleration cycle, the frequency of the accelerating voltage must track the steadily increasing magnetic field with high precision. The relative frequency error for a 1 cm displacement of the mean radius of the circulating particles in

to about 1 GeV, the accelerating voltage frequency is automatically determined from the magnetic field by an analogue computer having an accuracy of about one part in a thousand. At an energy very much less than 1 GeV, in the 100 MeV region when the particles are firmly captured in phase-stable bunches, another frequency controlled system is switched in supplementing the analogue computer. The second system uses pick-up electrodes to detect the phase of the bunches in the machine relative to the phase of the accelerating voltage frequency and, by means of a servo system, holds this phase difference constant at a prescribed value. In addition, the radial position of the circulating bunches of particles in the machine is detected by other pick-up electrodes and, by means of another servo system, the bunches are maintained in the centre of the vacuum chamber.

Apart from these specific problems peculiar to alternating gradient synchrotrons, there are general theoretical problems concerned with non-linear stability criteria which have been studied extensively. The CPS is equipped with sextupole and octupole lenses to adjust non-linearities in the magnetic field of the machine. A complete description of the CPS is in course of preparation (2) (4) (5). ***

Measurements so far carried out on the CPS are necessarily preliminary and incomplete. It will take at least six months of measurement work before sufficient is known about the behaviour of the machine to exploit it as a working nuclear physics tool.

The intensity of the proton beam is surprisingly high at this early stage of operation. Protons are injected into the synchrotron at an energy of 50 MeV from a proton linear accelerator whose design closely follows that developed at the Lawrence Radiation Laboratory, Berkeley. One important difference, however, is that the CPS linear accelerator contains magnetic quadrupole alternating gradient focusing in the drift tubes, in place of the grid focusing originally used in the American machine.

The CPS linear accelerator has produced intensities up to 5 mA peak, although for the tests so far carried out with the synchrotron a collimated 1 mA proton beam has been employed. A buncher and debuncher have been built for this linear accelerator, but neither have been used so far. With 1 mA being injected into the synchrotron and

Fig. 1 : Beam accelerated to about 24 GeV with no loss

particles approach the velocity of light, the velocity term decreases due to relativistic effects. Consequently, there comes a time in the acceleration cycle of the CPS when the radius term equals the velocity term. The energy at this time is called the "transition energy". At this energy the frequency of the synchrotron oscillation goes to zero, phase stability is lost, and a rapid shift in the phase of the accelerating voltage has to be made so as to recapture after transition energy all the particles that have been accelerated up to that energy.

It is possible to design an alternating gradient machine so that the transition energy is higher than the maximum energy of the machine,

the CPS is given in the following table :

Kinetic Energy of Protons	$\Delta f/f$ for 1 cm Radial Displacement
50 MeV (injection)	$3.5 \cdot 10^{-8}$
1 GeV	$8.3 \cdot 10^{-4}$
2 GeV	$2.7 \cdot 10^{-4}$
3 GeV	$1.2 \cdot 10^{-4}$
4 GeV	$4.5 \cdot 10^{-5}$
5 GeV (transition)	0
10 GeV	$7 \cdot 10^{-5}$
25 GeV	$7.5 \cdot 10^{-5}$

It can be seen that another unfortunate effect of the transition energy is to impose impossible tolerances on the accelerating voltage frequency at and near that energy. This problem has been solved in the CPS in the following manner. From the injection energy of 50 MeV

single turn injection, a capture efficiency of 20–25 % has been measured, corresponding to a circulating beam of 10^{10} protons per pulse. The pulse repetition rate at 25 GeV is 20 a minute.

The energy of the protons in the synchrotron has, so far, been calculated from the magnetic field at the time the beam disappears and the radius of the machine. The earliest operational runs were carried out without any of the correcting devices being employed, except for the self-powered pole face windings needed to correct eddy currents in the metal vacuum chamber at injection when the guiding magnetic field is only 140 gauss. The proton beam then disappeared at a magnetic field of about 12 Kgauss due to the number of free oscillations of the particles per revolution becoming an integer. As the magnet yoke saturates, the focusing forces diminish slightly, and instead of the machine working in the stable region between the unstable resonance bands, the operating point is slowly forced into a resonance and the particles are lost to the walls of the vacuum chamber. In later runs the pole face windings were energized by programmed generators designed to keep the focusing forces constant up to magnetic fields of over 14 000 gauss and it was observed that all of the proton beam then reached an energy of just over 28 GeV, limited only by the peak magnetic field available in the CPS.

An attempt has been made to measure the number of free oscillations per revolution in both the axial and radial directions (Q_v and Q_R) during the acceleration cycle. At injection, with the pulsed inflector voltages not energized and a $2\text{ }\mu\text{s}$ pulse of protons injected from the linear accelerator, the beam spirals inwards in radius due to the rising magnetic field for over one hundred microseconds, and the fractional Q -values can be observed in the two directions by pick-up electrodes sensitive to one or the other of the two directions of oscillation. For these measurements the beam is injected in such a way as to set up either axial or radial oscillations of the particles. During the acceleration cycle the Q -values were measured by pulsing the quadrupole correcting lenses at different times in the cycle and by variable amounts, and noting when the beam was lost. The nominal Q -values are both about 6.25, and if at a certain moment the quadrupole lenses are pulsed by an amount that shifts, say,

Above is a view taken during the construction of the PS, showing the ring tunnel and the linear accelerator wing (left) before the concrete structure was covered with earthfill. The photo on the right shows the 50 MeV linear accelerator tanks (30 m long) being aligned. The output end is in the foreground.

The PS magnet blocks (right) were stored in the South Experimental Hall prior to their assembling in 10-block units. Below is a view of the intricate cabling system running underground. In the PS, cable length amounts to some 3 600 km.

The south hall is the largest of the two intended to house the experimental apparatus to be used in connection with the PS. It covers 3 200 square metre.

A phase of the transport of a magnet unit into the ring tunnel. The unit rests on two pivoting bogies drawn by an electric tractor. The dark concrete girder designed to carry the synchrotron structure is architecturally independent of the building.

A view of the 50 MeV linear accelerator, showing the drift tubes mounted in one of the three tanks of the apparatus, before its cover was installed.

An alternating current generator driven by an induction motor at 3 000 rpm supplies 34 600 kW peak power to the magnet. An 8.6 ton fly-wheel (in front of operator) is used to store the energy recovered from the magnet.

the Q_R value to 6.0, the beam will be lost due to instability at a radial first resonance. Similarly, pulsing the lenses in the opposite direction by the same amount loses the beam due to instability at a radial second order resonance at $Q_R = 6.5$. Apart from the shift of the Q -values when the magnet saturates, it appears that they remain close to $Q_V = 6.3$, $Q_R = 6.2$ during most of the acceleration cycle. Using this same method, the unstable boundaries of the stable operating region, namely $Q_R = 6.0$, 6.5 and $Q_V = 6.0$, 6.5, have been measured. So far, no higher order resonances due to non-linear instabilities have been observed, although whether this is a tribute to the linearity of the machine or due to the crudeness of the measurements remains to be seen.

Measurements have been made of the closed orbit displacement at 20 points around the circumference of the machine, from which the closed orbit amplitude and shape have been computed. The closed orbit is that orbit around which all particles perform free oscillations. In a perfect machine without field free sectors it would be a perfect circle in a plane. In an imperfect machine its shape and amplitude are due to the imperfections. At injection the peak to peak amplitude of the closed orbit in the radial direction is about 4 cm, and in the axial direction it is a few mm. Later on in the cycle the peak to peak amplitude diminishes in the radial direction to about 1 cm and remains negligible in the axial direction. Since the vacuum chamber dimensions are 14 cm in the radial direction and 7 cm in the axial direction, there is therefore no danger of beam loss due to magnet misalignments.

The transition energy, which seemed so formidable a barrier during the design stage, proved to be easily surmountable in practice. The precision of phase switching needed at transition for no noticeable loss of particles was found to be about ± 3 ms, or ± 36 gauss.

Both the computer and the beam control system for determining the frequency of the accelerating voltage have proved very satisfactory after minor adjustments. During the operational runs so far carried out the beam control system has been switched in about 1 ms after injection and there seems to be no noticeable loss of particles during this switch-over. During the early acceleration studies the radial control servo acted on the amplitude of the accelerating voltage, which in principle is equally

effective a means of controlling the radial position of the beam as varying the phase or frequency of the accelerating voltage. This arrangement was not successful, perhaps due to a certain amount of jitter in the phase-lock loop, and the system was modified so that the radial control servo acted on the phase of the accelerating voltage. This second method was completely successful and no particles were lost during acceleration. Preliminary measurements indicated that the beam was not moving more than 1 cm from the centre of the vacuum chamber during the acceleration cycle. The beam control system depends for its operation on the presence of a bunched proton beam, and due to noise in the servo loops, there is a certain minimum value for the circulating beam current below which the system no longer maintains control. It appears from early measurements that the system will work with about 10^8 protons per pulse.

A very important parameter of an accelerator is the mean intensity. Fig. 2 shows that at an energy of 6 GeV the mean intensity of the CPS is now nearly as high as that of the Bevatron, and at 10 GeV considerably higher than that of the Russian machine. It is hoped to increase the intensity of the CPS by an order of magnitude by bringing into operation the buncher and debuncher of the linear accelerator and allowing more protons to be injected into the synchrotron. At 25 GeV the yield of secondary particles from internal targets is considerably higher than at 6–10 GeV, and early measurements of secondary particle yields from the CPS indicate that the machine may be a strong competitor to the lower energy high intensity machines now being built from this point of view.

* * *

The significance of this accelerating machine can best be understood in relation to other proton synchrotrons. The CPS accelerates protons to an energy which is about three times the energy of the largest accelerator now functioning, namely the Russian Synchrophasotron at Dubna, and so, for a while, Europe possesses by far the largest accelerator in the world. In 1960 another machine of slightly higher energy (30 GeV) will come into operation at Brookhaven in America, and in 1962 or thereabouts the Russians plan to bring into operation a machine twice as large as the CPS (50 GeV). The possession of the world's highest energy accelerator is, and always has

Accelerator	Max. energy GeV	Mean intensity Particles per sec.	Completion date
Brookhaven proton synchrotron (COSMOTRON)	3	2.10^{10}	1952
Saclay proton synchrotron (SATURNE) .	3	10^{10}	1958
Princeton-Pennsylvania proton synchrotron	3	2.10^{12*}	1960
Berkeley proton synchrotron (BEVATRON)	6	2.10^{10}	1954
Rutherford Laboratory proton synchrotron (NIMROD)	7	10^{12*}	1961/62
Russian A.G. proton synchrotron . . .	7	$\approx 2.10^9*$	1960
Russian proton synchrotron (Synchrophasotron)	10	$\approx 10^9$	1957
Australian proton synchrotron	10	10^7*	1962/63
Argonne zero gradient proton synchrotron	12.5	2.10^{12*}	1962
CERN proton synchrotron	28	2.10^9	1959
	25	3.10^9	
	6-10	10^{10}	
Brookhaven A.G. proton synchrotron .	30	$\approx 3.10^9*$	1960
Russian A.G. proton synchrotron . . .	50	$\approx 10^9*$	1961/62

Fig. 2 : Proton accelerators.

(*) indicates target figures.

been, a transitory state, but the remarkable significance of this event is that for the first time for over twenty years Europe can claim this possession. Since the war a major effort has been made in Europe to equip laboratories working in high energy nuclear physics research with the necessary apparatus. The magnitude of this effort in terms of money is considerable, as can be seen in the following table :

	Maximum Energy	Cost in Million Sw. Fr.
CERN Proton Synchr.	28 GeV	120
Rutherford Laboratory Proton Synchrotron	7 GeV	84
Saclay Proton Synchr.	3 GeV	53
Hamburg Electr. Synchr.	6 GeV	60

The cost of running these laboratories and building apparatus for the experiments is equally high, and this is a recurrent cost since new experimental apparatus is continuously being needed as the experiments develop. For example, the annual budget of CERN, which in addition to the CPS also has a 600 MeV Synchro-cyclotron, is about Sw. Fr. 60 million per annum.

That Europe has made such an effort in this field of fundamental research has been due to the foresight of the physicists who have planned the laboratories and the sympathy of the governments who have supplied the money ●

REFERENCES

- (1) Physical Review, Vol. 88 (5), pp 1190-1196, 1952. « The Strong-Focusing Synchrotron, a New High Energy Accelerator » — E. D. Courant, M. S. Livingston, H. S. Snyder.
- (2) CERN 59-29. « The CERN Proton Synchrotron, Part 1. Ch. I : Basic Principles of Alternating Gradient Synchrotrons. Ch. II : Design of the CPS and Choice of Parameters. Ch. III : Magnet. Ch. IV : The Radio Frequency Acceleration System. » — E. Regenstein.
- (3) CERN 56-21. « The Design of the Foundations for the Magnet of the CERN Alternating Gradient Proton Synchrotron » — J. B. Adams.
- (4) CERN 59-26. Le Synchrotron à Protons du CERN, 2e partie. Chap. V : L'injection des particules. » — E. Regenstein. (English version to be published.)
- (5) CERN... « The CERN Proton Synchrotron, Part 3. » — E. Regenstein. (To be published.)